Advertisement For Bids

Shuttle Hardscape Additional Repairs

The Alabama Space Science Exhibit Commission DBA U.S. Space & Rocket Center seeks proposals from qualified firms for additional maintenance repairs of the existing Space Shuttle Hardscape.

General Specifications:

- Use ½" wood fiber expansion joint fillers in expansion joints between concrete slabs of differing types to prevent concrete damage due to expansion and contraction.
- Use additional control joints as needed to prevent random, unsightly surface fractures.
- All areas should use 6"x6" wire mesh reinforcement.

Site Specific Scope of Work:

- Demolish and haul off approximately 5,484 SF of existing concrete beneath the Pathfinder shuttle, averaging 6" thick.
- Thoroughly protect all shuttle supports during demolition and concrete placement.
- Furnish and install welded wire mesh, approximately 55 sheets of 10'x20' 6x6 WWM.
- Furnish and install four (4) Quazite underground enclosure assemblies, 28 1/2" x 15 1/2" x 10" usable interior, open bottom, at the four junction box locations.
- Place and finish approximately 102 CY of concrete at an average depth of 6".

All potential bidders may request via email a copy of all project drawings and additional specifications related to this bid. Drawings and Specifications may also be examined at the office of the Director of Procurement, U.S. Space and Rocket Center, One Tranquility Base, Huntsville, Al 35805

A mandatory Prebid meeting being held on **11/05/26 at 9:00AM CST** in the Main Lobby of the Administrative Entrance located at the U.S. Space and Rocket Center, 1 Tranquility Base, Huntsville, Al 35805

Bids must be submitted on DCM C-3 Bid Proposal forms. Additional documentation includes a detailed Itemized Quote on Vendor Letterhead, Certificate of Insurance, E-Verify, Al Vendor Disclosure Statement, and W9 form. Payment, Performance, and Bid Bonds are required for this maintenance project.

All bidders bidding in amounts exceeding that established by the State Licensing Board for General Contractors must be licensed under the provisions of Title 34, Chapter 8, Code of Alabama, 1975 and must show evidence of license before bidding or bid will not be received or considered by the Owner. The Owner reserves the right to reject any or all proposals and to waive technical errors if, in the Owner's judgement, the best interests of the Owner will thereby be promoted.

Sealed proposals will be received by the U.S. Space and Rocket Center Commission at the office of Sam Mitchell, Director of Procurement, U.S. Space and Rocket Center, at the ETF Building 1st Floor, One Tranquility Base, Huntsville, Al 35805 until **11/17/26 at 2:00pm CST**. At which time and place, each seal bids will be publicly opened and read into the record.

You may also submit your seal bid prior to public bid opening to the Director of Procurement, for the U.S. Space and Rocket Center, by coming in person to the Administration Entrance located at the U.S. Space and Rocket Center, One Tranquility Base, Huntsville, Al 35805. You may also mail your seal bid using a reliable & trackable delivery method to the street address listed and by the time and due date shown.

Electronic Bids submitted via Email will be accepted provided they are received by the time and due date shown above.